

KONE JUMPLIFT™



GENERAL CONTRACTOR'S REQUIREMENTS

- Removable Deflection Deck or flat Retaining Deck as specified in site specific KONE jump plan and purchasing agreement. **A**
- Double Protection Deck is provided by KONE. The deck will be relocated and sealed watertight according to agreement. The upper deck must be watertight and the lower deck must have fixing points for installation equipment. **B**
- Block-outs in the shaft walls for the Double Protection Deck, separation deck, lifting beam, and mobile machine room as specified KONE drawings and in accordance with code requirements. **C**
- Finished floor level mark inside elevator shaft at each landing (normally the builder puts these marks outside and the installer transfers them from the landing).
- Adequate power supply for the mobile machine room, hoists, power tools, and lighting, as specified in the KONE jump plan. **D**
- Support for transporting elevator construction materials to predefined floors; KONE will verify floors and staging loadings with the builder in advance.
- Adequate protection for landing door entrances.
- A dry and wind-free area below the Double Protection Deck incorporating full-height, imperforate entrance protection to open landing entrances.
- A closed, lockable area adjacent to the pit area or lowest floor, for the rope reels (where applicable), power cable, and main isolator/main disconnect. **E**
- Fixed, debris-free stair access to, and continuous lighting for, all floors served by the JumpLift up to the Double Protection Deck.
- Flat, step-free access or temporary ramps to the JumpLift car.
- Intercom, telephone and tele-surveillance connection inside the elevator per code requirements and purchasing agreement.
- If possible, appoint a dedicated elevator attendant.
- All necessary climate control devices in the mobile machine room and rope reel room according to the purchasing agreement.
- Keeping lobby area accessible and tidy.

Full details can be obtained from your local KONE contact

KONE
kone.us

